The quantities shown in this quantity table come from Examples "A-1" and "A-2."

In this example, the Traffic Stripe Detail Numbers are listed within the "header" of the quantity table.

PAVEMENT DELINEATION QUANTITIES

SHEET No.	LOCATION/STATION	DIRECTION	THERMOPLASTIC TRAFFIC STRIPE									THERMOPLASTIC PAVEMENT MARKING				REMOVE PAINTED PAVEMENT MARKING	PAVEMENT MARKER				DELINEATOR (CLASS 1)		DESCRIPTION/ COMMENTS
			4" WHITE					4" YELLOW	8" WHITE								NON-REFLECTIVE	RETROREFLECTIVE					
			DETAIL 8/10	DETAIL 11/13	DETAIL 11/14	DETAIL 25	DETAIL 25A	DETAIL 27B	DETAIL 36	DETAIL 37	DETAIL 38B	TYPE V ARROW	TYPE VI ARROW	"SIGNAL"	"AHEAD"		TYPE A	TYPE C	TYPE G	TYPE H	TYPE F	TYPE G	
			LF	LF	LF	LF	LF	LF	LF	LF	LF	SQFT	SQFT	SQFT	SQFT	SQFT	EA	EA	EA	EA	EA	EA	
PD-1 - PD-2	"B" 845+00 TO 855+30	WB						1,030															
PD-1 - PD-2	"B" 845+00 TO 862+45	WB		3,490													296		74				2 TRAFFIC STRIPES
PD-1 - PD-2	"B" 845+00 TO 864+50	WB				1,950														42			
PD-2	"B" 854+20 TO 858+00	WB											126										3 EACH
PD-2	"B" 854+20 TO 862+45	WB		825													72		18				
PD-2	"ENRA" 851+50 TO "B" 862+00	WB																			10		
PD-2	"ENRA" 852+32 TO "B" 864+50	WB						1,218															
PD-2	"ENRA" 852+32 TO 853+32	WB																				3	
PD-2	"ENRA" 852+32 TO 858+00	WB	568														72		13				
PD-2	"ENRA" 852+32 TO 855+32	WB					300													14			
PD-2	"ENRA" 853+54	WB										66											2 EACH
PD-2	"ENRA" 854+55	WB													62								2 EACH
PD-2	"ENRA" 854+67	WB														33							TYPE V ARROW
PD-2	"ENRA" 855+02	WB														31							"AHEAD"
PD-2	"ENRA" 855+10	WB												64									2 EACH
PD-2	"ENRA" 855+22	WB														32							"SIGNAL"
PD-2	"ENRA" 855+32 TO 858+00	WB							268										12				
PD-2	"B" 855+30 TO 858+00	WB							270										12				
PD-2	"ENRA" 858+00 TO "B" 862+45	WB									445								40				
PD-2	"B" 862+45 TO 864+50	WB								205								8	10				
PD-2	"B" 862+45 TO 863+89	WB			432												36	12					3 TRAFFIC STRIPES
PD-2	"B" 863+89 TO 864+50	WB		183													24		9				3 TRAFFIC STRIPES
SUBTOTAL			568	4,498	432	1,950	300	2,248	538	205	445	66	126	64	62			20	188	56	10	3	
TOTAL			9,996						1,188			318				96	500	264			13		

PAVEMENT DELINEATION QUANTITIES SHEET, EXAMPLE "A-3"

PAVEMENT DELINEATION QUANTITIES

PDQ-2

REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE

REGISTERED PROFESSIONAL ENGINEER No. Exp. CIVIL STATE OF CALIFORNIA

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS

PAVEMENT DELINEATION QUANTITIES SHEET, EXAMPLE "A-3" RELEASED 4/20/2011

LAST REVISION 00-00-00

REVISED BY | DATE REVISED

CALCULATED-DESIGNED BY | CHECKED BY

FUNCTIONAL SUPERVISOR

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION

Caltrans

BORDER LAST REVISED 7/2/2010

USERNAME => trjck
DGN FILE => PDQuantities_Example_A-3.dgn

RELATIVE BORDER SCALE IS IN INCHES 0 1 2 3

UNIT 0000

PROJECT NUMBER & PHASE 00000000001