


Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
03	Pla	65	R11.9/R24.1		

REGISTERED CIVIL ENGINEER	DATE
PLANS APPROVAL DATE	



THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

PLACE HOT MIX ASPHALT DIKE

LOCATION	STATION	TYPE C	TYPE E	TYPE F	HOT MIX ASPHALT (TYPE A) TON
		LF	LF	LF	
ROUTE 65 "D13" - R+	677+00.48 TO 677+25.26	24.9			0.2
ROUTE 65 "D13" - R+	677+25.26 TO 677+49.99			24.9	0.3
ROUTE 65 "D13" - L+	707+36.14 TO "F6" 716+09+36	54.1	792.0	24.9	11.7
ROUTE 65 "D13" - R+	704+61.80 TO 705+14.68	38.1		24.9	0.6
ROUTE 65 "D13" - R+	719+90.04 TO 720+42.86	38.1		24.9	0.6
ROUTE 65 "D13" - L+	729+62.28 TO 729+87.21			24.9	0.3
ROUTE 65 "D13" - L+	729+87.21 TO 730+24.71	37.4			0.2
ROUTE 65 "D13" - R+	763+67.85 TO 763+92.62	24.9			0.2
ROUTE 65 "D13" - R+	763+92.62 TO 764+17.42			24.9	0.3
ROUTE 65 "D13" - R+	881+79.69 TO 882+18.17	37.4			0.2
ROUTE 65 "D13" - R+	882+18.17 TO 882+43.11			24.9	0.3
ROUTE 65 "D13" - R+	934+26.95 TO 934+64.45			37.4	0.3
ROUTE 65 "D13" - R+	"NB10" 1049+33.41 TO 1049+70.91	37.4			0.2
ROUTE 65 "D13" - R+	1049+70.91 TO 1049+95.84			24.9	0.3
ROUTE 65 "D13" - R+	1117+40.94 TO 1117+78.24	37.4			0.2
ROUTE 65 "D13" - R+	1117+78.24 TO 1118+03.17			24.9	0.3
ROUTE 65 "D13" - R+	1163+60.71 TO 1163+98.21			37.4	0.4
ROUTE 65 "D13" - R+	1173+94.50 TO 1174+31.99	37.4			0.2
ROUTE 65 "D13" - R+	1174+30.99 TO 1174+56.93			24.9	0.3
DOWD ROAD "DOWF1" - L+	1171+41.35 TO 1171+79.70	37.4			0.2
DOWD ROAD "DOWF1" - L+	1171+79.70 TO 1172+04.63			24.9	0.3
NICOLAUS ROAD "NIC1" - R+	39+46.84 TO 45+62.49		615.5		13.4
NICOLAUS ROAD "NIC1" - R+	45+62.49 TO 46+49.85	87.3			0.7
NICOLAUS ROAD "NIC1" - R+	49+42.93 TO 50+05.37	62.3			0.4
NICOLAUS ROAD "NIC1" - R+	50+05.37 TO 54+69.14		463.9		10.1
NICOLAUS ROAD "NIC1" - L+	39+46.84 TO 45+77.15		630.2		13.7
NICOLAUS ROAD "NIC1" - L+	45+77.15 TO 46+39.59	62.3			0.4
NICOLAUS ROAD "NIC1" - L+	49+32.66 TO 50+20.03	87.3			0.7
NICOLAUS ROAD "NIC1" - L+	50+20.03 TO 54+69.14		449.1		9.8
NORTH FARM ROAD "NOF1" - R+	162+08.78 TO 162+46.18	37.4			0.3
NORTH FARM ROAD "NOF1" - R+	162+46.18 TO 162+71.21			24.9	0.2
NORTH FARM ROAD "NOF1" - R+	165+41.88 TO 165+66.81				0.2
NORTH FARM ROAD "NOF1" - R+	165+66.81 TO 166+01.03	37.4			0.3
NORTH FARM ROAD "NOF1" - L+	162+07.83 TO 162+32.86	37.4			0.3
NORTH FARM ROAD "NOF1" - L+	162+32.86 TO 162+70.26			24.9	0.2
NORTH FARM ROAD "NOF1" - L+	162+09.01 TO 162+46.41			24.9	0.2
NORTH FARM ROAD "NOF1" - L+	162+46.41 TO 162+71.44	37.4			0.3
TOTAL		853.3	2950.7	423.4	68.8*

* QUANTITY INCLUDED IN PAVEMENT STRUCTURE QUANTITIES SUMMARY.

CURB RAMPS

LOCATION	STATION	MINOR CONCRETE (CURB RAMP) CY
INDUSTRIAL Ave "IND1" - R+	40+41.33	2.90
INDUSTRIAL Ave "IND1" - R+	41+46.96	5.18
INDUSTRIAL Ave "IND1" - R+	44+51.43	2.12
INDUSTRIAL PARK AND RIDE PERIMETER	44+94.73	2.80
CURB RAMPS AT PARK AND RIDE	RAMP #1	0.76
CURB RAMPS AT PARK AND RIDE	RAMP #2	0.76
CURB RAMPS AT PARK AND RIDE	RAMP #3	0.76
CURB RAMPS AT PARK AND RIDE	RAMP #4	0.55
CURB RAMPS AT PARK AND RIDE	RAMP #5	3.94
INDUSTRIAL Ave "IND1" - R+	49+38.43 TO 49+70.89	3.90
INDUSTRIAL Ave "IND1" - R+	50+22.20 TO 50+41.02	2.18
INDUSTRIAL Ave "IND1" - R+	59+52.14 TO 59+68.55	3.57
INDUSTRIAL Ave "IND1" - R+	71+37.81 TO 71+50.63	1.75
FERRARI RANCH ROAD "FR" - L+	70+78.56 TO 70+88.91	2.22
FERRARI RANCH ROAD "FR" - L+	71+32.90 TO 71+61.21	4.80
FERRARI RANCH ROAD "FR" - L+	71+85.16 TO 72+09.13	4.11
FERRARI RANCH ROAD "FR" - L+	72+21.97 TO 72+32.72	2.34
FERRARI RANCH ROAD "FR" - L+	80+99.16 TO 81+17.20	2.47
FERRARI RANCH ROAD "FR" - L+	81+20.00 TO 81+31.74	2.03
FERRARI RANCH ROAD "FR" - L+	81+70.26 TO 81+87.35	2.62
FERRARI RANCH ROAD "FR" - L+	81+89.90 TO 82+03.25	2.33
FERRARI RANCH ROAD "FR" - R+	80+98.39 TO 81+21.55	3.37
FERRARI RANCH ROAD "FR" - R+	81+24.73 TO 81+36.32	1.78
FERRARI RANCH ROAD "FR" - R+	82+10.82 TO 82+23.83	2.15
NICOLAUS ROAD "NIC1" - L+	46+14.65 TO 46+39.58	2.24
NICOLAUS ROAD "NIC1" - R+	46+24.92 TO 46+49.85	2.24
NICOLAUS ROAD "NIC1" - L+	49+32.66 TO 49+57.59	2.24
NICOLAUS ROAD "NIC1" - R+	49+42.93 TO 49+67.86	2.24
TOTAL		70.35

(N) - NOT A SEPARATE BID ITEM

SIDEWALK QUANTITIES

LOCATION	STATION	MINOR CONCRETE (SIDEWALK)	CLASS 2 AGGREGATE BASE	REMOVE SIDEWALK
		CY	CY	SQYD
INDUSTRIAL Ave "IND1" - R+	39+24.22 TO 40+27.94	9.9	9.9	
INDUSTRIAL Ave "IND1" - R+	41+60.35 TO 44+49.38	47.2	47.2	
INDUSTRIAL Ave "IND1" - R+	44+98.80 TO 49+32.08	47.0	47.0	
INDUSTRIAL PARK AND RIDE PERIMETER	61.4' R+ 40+50.24 TO 328.1' R+ 42+07.78	102.8	102.8	
INDUSTRIAL PARK AND RIDE INTERIOR	328.1' R+ 42+07.78 TO 328.1' R+ 44+15.34			
INDUSTRIAL PARK AND RIDE INTERIOR	76.1' R+ 41+34.46 TO 299.5' R+ 42+11.72	32.0	32.0	
INDUSTRIAL Ave "IND1" - R+	49+22.19 TO 49+74.91	5.8	7.6	
INDUSTRIAL Ave "IND1" - R+	50+17.02 TO 59+70.84	113.8	151.7	
INDUSTRIAL Ave "IND1" - R+	71+35.33 TO 72+32.54	10.6	14.1	
FERRARI RANCH ROAD "FR" - L+	70+43.94 TO 70+96.43	7.7	10.3	
FERRARI RANCH ROAD "FR" - L+	72+17.82 TO 75+13.10	44.1	58.7	
FERRARI RANCH ROAD "FR" - L+	81+03.65 TO 81+36.45	5.5	7.5	
FERRARI RANCH ROAD "FR" - L+	81+85.67 TO 86+61.39	67.9	90.6	
FERRARI RANCH ROAD "FR" - R+	81+20.05 TO 81+39.73	6.3	8.2	
FERRARI RANCH ROAD "FR" - R+	82+02.07 TO 82+44.72	5.6	7.5	
FERRARI RANCH ROAD "FR" - L+	85+79.37 TO 86+58.11			23.88
TOTAL		506.2	595.1*	23.88

* QUANTITY INCLUDED IN PAVEMENT STRUCTURE QUANTITIES SUMMARY.

THIS EXAMPLE IS ONE OF MANY EXAMPLES OF THE VARIOUS TYPES OF PROJECT PLAN SHEETS FROM THE SAME CONSTRUCTION PROJECT, "ROUTE 65 BYPASS PROJECT."

SUMMARY OF QUANTITY SHEET, EXAMPLE "65 Q-11"

SUMMARY OF QUANTITIES

Q-11

