

DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30th Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

www.dot.ca.gov/hq/esc/oe



*Serious Drought.
Help save water!*

October 17, 2016

01-Hum-101-111.3/111.7

01-OB4304

Project ID 0112000127

ACNH-ER-19D3(004)E

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN HUMBOLDT COUNTY NEAR BIG LAGOON FROM 1.8 MILES TO 2.2 MILES NORTH OF GEORGIA PACIFIC ROAD to revise the project plans, the *Notice to Bidders and Special Provisions*, and the *Bid book*.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Tuesday, November 15, 2016.

Project plan sheets 19 and 20 are replaced and attached for substitution for the like-numbered sheets.

Project plan sheet 50 is deleted.

In the Notice to Bidders, the following paragraph is added after the ninth paragraph as follows:

"For the Federal training program, the number of trainees or apprentices is 1."

In the Special Provisions, Section 20-1.03C, is added as attached.

In the Special Provisions, DIVISION III "GRADING," is deleted.

In the *Bid book*, in the "Bid Item List," Items 55, 59 and 89 are replaced.

Addendum No. 1
Page 2
October 17, 2016

01-Hum-101-111.3/111.7
01-0B4304
Project ID 0112000127
ACNH-ER-19D3(004)E

To *Bid* book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the *Notice to Bidders* section of the *Notice to Bidders and Special Provisions*.

Submit the *Bid* book as described in the *Electronic Bidding Guide* at the Bidders' Exchange website.

http://www.dot.ca.gov/hq/esc/oe/electronic_bidding/electronic_bidding.html

Inform subcontractors and suppliers as necessary.

This addendum, EBS addendum file and attachments are available for the Contractors' download on the Web site:

http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/01/01-0B4304

If you are not a *Bid* book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



CHARLIE FIELDER
District Director

Attachments

Delete para 5 section 20-1.01A of the RSS

Replace section 20-1.03C of the RSS with:

20-1.03C Invasive Species Removal

Section 20-1.03C includes specifications for invasive species removal.

Invasive plants are Scotch Broom, Jubata Grass, Fennel, and Spanish Heather.

Notify the Engineer a minimum of 15 days prior to clearing and grubbing to allow a Department biologist to provide information on identification of invasive plants. The Department biologist or revegetation specialist must be present during invasive plant removal.

Remove invasive plants prior to performing clearing and grubbing.

Invasive plants adjacent to the right edge of pavement must be removed by hand-pulling.

Backfill holes resulting from invasive plant removal to the original ground with topsoil the same day that invasive plants are removed. Dispose of invasive plants at commercial disposal facility. Roadside drop-off or green waste disposal is not permitted. Provide receipts for disposal fees to the Engineer.

Remove and dispose uprooted invasive plants within the same day.

BID ITEM LIST
01-0B4304

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
41	152299	RESET MILEPOST MARKER	EA	2		
42	152316	RESET ROADSIDE SIGN (ONE POST)	EA	1		
43	153103	COLD PLANE ASPHALT CONCRETE PAVEMENT	SQYD	1,750		
44	160102	CLEARING AND GRUBBING (LS)	LS	LUMP SUM	LUMP SUM	
45	170101	DEVELOP WATER SUPPLY	LS	LUMP SUM	LUMP SUM	
46	190101	ROADWAY EXCAVATION	CY	1,300		
47	190185	SHOULDER BACKING	TON	55		
48(F)	192049	STRUCTURE EXCAVATION (SOLDIER PILE WALL)	CY	690		
49(F)	193029	STRUCTURE BACKFILL (SOLDIER PILE WALL)	CY	310		
50(F)	193116	CONCRETE BACKFILL (SOLDIER PILE WALL)	CY	975		
51(F)	193119	LEAN CONCRETE BACKFILL	CY	54		
52	032427	INVASIVE SPECIES REMOVAL	LS	LUMP SUM	LUMP SUM	
53	032428	CONTRACTOR SUPPLIED ARBORIST	LS	LUMP SUM	LUMP SUM	
54	032429	SOIL AMENDMENT (CF)	CF	18		
55	202037	ORGANIC FERTILIZER	LB	0.5		
56	204099	PLANT ESTABLISHMENT WORK	LS	LUMP SUM	LUMP SUM	
57	205035	WOOD MULCH	CY	190		
58	032430	DUFF (SQFT)	SQFT	2,350		
59	210260	ROLLED EROSION CONTROL PRODUCT (JUTE MESH)	SQFT	26,800		
60	210270	ROLLED EROSION CONTROL PRODUCT (NETTING)	SQFT	21,400		

BID ITEM LIST
01-0B4304

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
81	665024	24" CORRUGATED STEEL PIPE (.109" THICK)	LF	48		
82	680902	6" PERFORATED PLASTIC PIPE UNDERDRAIN	LF	146		
83	680903	6" NON-PERFORATED PLASTIC PIPE UNDERDRAIN	LF	113		
84	690124	24" CORRUGATED STEEL PIPE DOWNDRAIN (.109" THICK)	LF	21		
85	692309	24" ANCHOR ASSEMBLY	EA	2		
86	721015	ROCK SLOPE PROTECTION (LIGHT, METHOD B) (CY)	CY	8		
87	721017	ROCK SLOPE PROTECTION (FACING, METHOD B) (CY)	CY	2.3		
88	729011	ROCK SLOPE PROTECTION FABRIC (CLASS 8)	SQYD	37		
89	820112	MARKER (CULVERT)	EA	3		
90	820134	OBJECT MARKER (TYPE P)	EA	2		
91	032432	CRASH CUSHION (TYPE TRACC)	EA	2		
92(F)	045622	CALIFORNIA ST-10 BRIDGE RAIL (MODIFIED) WITH BICYCLE RAILING	LF	119		
93	840504	4" THERMOPLASTIC TRAFFIC STRIPE	LF	7,560		
94	850122	PAVEMENT MARKER (RETROREFLECTIVE-RECESSED)	EA	160		
95	999990	MOBILIZATION	LS	LUMP SUM	LUMP SUM	

TOTAL BID

FOR BID ITEMS:

\$

TOTAL BID

FOR TIME:

$$\frac{\text{WORKING DAYS BID}}{\text{(Do not bid less than 170 days and not more than 240 Days)}} \times \frac{\$5,400.00}{\text{COST PER DAY}} = \$$$

TOTAL BID FOR COMPARISON (COST PLUS TIME):

\$
