

**DEPARTMENT OF TRANSPORTATION**

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30<sup>th</sup> Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

www.dot.ca.gov/hq/esc/oe



*Serious Drought.  
Help save water!*

August 14, 2015

05-Mon-101-55.2/73.8

05-1F69U4

Project ID 0515000041

ACNHP-Q101(276)E

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN MONTEREY COUNTY IN AND NEAR SOLEDAD AND GONZALES FROM 0.4 MILE NORTH OF NORTH GREENFIELD OVERCROSSING TO 1.2 MILES NORTH OF NORTH GONZALES OVERCROSSING.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Thursday, September 10, 2015.

This addendum is being issued to revise the project plans, the *Notice to Bidders and Special Provisions*, and the *Bid* book.

Project plan sheets 118 and 123 are replaced and attached for substitution for the like-numbered sheets.

In the Special Provisions, Section 9, "PAYMENT," is replaced as follows:

**"Add to section 9-1.16C:**

The following items are eligible for progress payment even if they are not incorporated into the work:

1. Precast Jointed Concrete Pavement
2. Drill and Bond (Dowel Bar)
3. Guardrail Elements and End Treatment Terminal Systems
4. Culvert Pipes
5. Overside Drains and Appurtenances
6. Guardrail and End Treatment Systems
7. Pavement Markers
8. Lighting Standards
9. Luminaires"

05-Mon-101-55.2/73.8  
05-1F69U4  
Project ID 0515000041  
ACNHP-Q101(276)E

In the Special Provisions, Section 37, "BITUMINOUS SEALS," the first paragraph is deleted.

In the Special Provisions, Section 40-8.01A, "Summary," the fourth paragraph is replaced as follows:

"Install dowel bars at joints between PJCP and the existing concrete in compliance with the requirement in section 41-11, "Dowel Bar Slots" of these special provisions."

In the Special Provisions, Section 40-8.02D, "Expansion Cap," the first paragraph is replaced as follows:

"Expansion cap must comply with section 41-11, "Dowel Bar Slots"."

In the Special Provisions, Section 40-8.03A, "General," the second sentence of second paragraph is replaced as follows:

"If installation of the PJCP is not completed during the same lane closure, comply with the specifications for temporary roadway pavement structure in section 41-1.02E "Temporary Pavement Structure"."

In the Special Provisions, Section 40-8.03C(2), "Backfilling," the first paragraph is replaced as follows:

"Fill dowel bar slots in the PJCP and existing concrete pavement as soon as possible after panel placement and prior to opening to traffic. Fill dowel bar slots with polyester concrete in accordance with section 41-11, "Dowel Bar Slots" in these special provisions."

In the Special Provisions, Section 40-8.03E, "Isolation Joint," is added as follows:

"Longitudinal isolation joint must comply with section 40-1.03D(4), Isolation Joints in the RSS."

In the Special Provisions, Section 41-11.04, "Payment," is replaced as follows:

"Payment for the dowel bar slot is included in payment for precast jointed concrete pavement.

Grinding is not included in payment for precast jointed concrete pavement."

In the Special Provisions, Section 73, "CONCRETE CURBS AND SIDEWALKS," the following paragraph is added before the first paragraph.

**"Replace the paragraph in the RSS of section 73-1.01A with:**

Section 73-1 includes general specifications for constructing minor concrete items including concrete curbs, dikes, sidewalks, gutter depressions, driveways, island paving, and curb ramps; for installing detectable warning surfaces and precast parking bumpers; and for texturing and coloring concrete surfaces."

The *Information Handout* "Materials Information" is added as attached.

Addendum No. 1  
Page 3  
August 14, 2015

05-Mon-101-55.2/73.8  
05-1F69U4  
Project ID 0515000041  
ACNHP-Q101(276)E

In the *Bid* book, in the "Bid Item List," Item 67 is replaced.

In the *Bid* book, in the "Bid Item List," Item 115 and 116 are added.

In the *Bid* book, in the "Bid Item List," Items 64 and 114 are deleted.

To *Bid* book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the *Notice to Bidders* section of the *Notice to Bidders and Special Provisions*.

Submit the *Bid* book as described in the *Electronic Bidding Guide* at the Bidders' Exchange website.

**[http://www.dot.ca.gov/hq/esc/oe/electronic\\_bidding/electronic\\_bidding.html](http://www.dot.ca.gov/hq/esc/oe/electronic_bidding/electronic_bidding.html)**

Inform subcontractors and suppliers as necessary.

This addendum, EBS addendum file and attachments are available for the Contractors' download on the Web site:

**[http://www.dot.ca.gov/hq/esc/oe/project\\_ads\\_addenda/05/05-1F69U4](http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/05/05-1F69U4)**

If you are not a *Bid* book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



SHARRI BENDER EHLERT  
District Director  
District 6 Central Region

Attachments

**BID ITEM LIST  
05-1F69U4**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
61	397005	TACK COAT	TON	230		
62	029362	PRECAST JOINTED CONCRETE PAVEMENT	CY	2,740		
63	410096	DRILL AND BOND (DOWEL BAR)	EA	12,200		
64	BLANK					
65	410120	SPALL REPAIR (POLYESTER CONCRETE)	SQYD	240		
66	411105	INDIVIDUAL SLAB REPLACEMENT (RSC)	CY	3,390		
67	420201	GRIND EXISTING CONCRETE PAVEMENT	SQYD	85,100		
68	510502	MINOR CONCRETE (MINOR STRUCTURE)	CY	12		
69	510526	MINOR CONCRETE (BACKFILL)	CY	26		
70	560245	FURNISH LAMINATED PANEL SIGN (1"-TYPE B)	SQFT	59		
71	560246	FURNISH LAMINATED PANEL SIGN (2 1/2"-TYPE B)	SQFT	150		
72	560249	FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-UNFRAMED)	SQFT	220		
73	560252	FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-FRAMED)	SQFT	75		
74	566011	ROADSIDE SIGN - ONE POST	EA	9		
75	566012	ROADSIDE SIGN - TWO POST	EA	2		
76	568023	INSTALL ROADSIDE SIGN (LAMINATED WOOD BOX POST)	EA	2		
77	029364	FURNISH SINGLE SHEET ALUMINUM SIGN (0.080"-FRAMED) FOR RETROREFLECTIVE SHEETING (TYPE XI)	SQFT	56		
78	029365	RETROREFLECTIVE SHEETING (TYPE XI)	SQFT	56		
79	650010	12" REINFORCED CONCRETE PIPE	LF	35		
80	650014	18" REINFORCED CONCRETE PIPE	LF	460		

**BID ITEM LIST  
05-1F69U4**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
101	839585	ALTERNATIVE FLARED TERMINAL SYSTEM	EA	25		
102	839701	CONCRETE BARRIER (TYPE 60)	LF	720		
103	029367	CONCRETE BARRIER (TYPE 60SD)	LF	690		
104	840504	4" THERMOPLASTIC TRAFFIC STRIPE	LF	433,000		
105	840506	8" THERMOPLASTIC TRAFFIC STRIPE	LF	21,300		
106	840515	THERMOPLASTIC PAVEMENT MARKING	SQFT	6,500		
107	840525	4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 36-12)	LF	197,000		
108	840526	4" THERMOPLASTIC TRAFFIC STRIPE (BROKEN 17-7)	LF	2,610		
109	850101	PAVEMENT MARKER (NON-REFLECTIVE)	EA	16,400		
110	850111	PAVEMENT MARKER (RETROREFLECTIVE)	EA	10,200		
111	860090	MAINTAINING EXISTING TRAFFIC MANAGEMENT SYSTEM ELEMENTS DURING CONSTRUCTION	LS	LUMP SUM	LUMP SUM	
112	860807	INDUCTIVE LOOP DETECTOR (LS)	LS	LUMP SUM	LUMP SUM	
113	861503	MODIFY LIGHTING	LS	LUMP SUM	LUMP SUM	
114	BLANK					
115	414240	ISOLATION JOINT SEAL (ASPHALT RUBBER)	LF	6,870		
116	999990	MOBILIZATION	LS	LUMP SUM	LUMP SUM	

**TOTAL BID:**

**\$**

---