

DEPARTMENT OF TRANSPORTATION

DES-OE MS #43
1727 30TH Street, 2ND Floor
Sacramento, CA 95816



**** WARNING ** WARNING ** WARNING ** WARNING ****
This document is intended for informational purposes only.

Users are cautioned that California Department of Transportation (Department) does not assume any liability or responsibility based on these electronic files or for any defective or incomplete copying, excerpting, scanning, faxing or downloading of the contract documents. As always, for the official paper versions of the bidders packages and non-bidder packages, including addenda write to the California Department of Transportation, Plans and Bid Documents, Room 0200, P.O. Box 942874, Sacramento, CA 94272-0001, telephone (916) 654-4490 or fax (916) 654-7028. Office hours are 7:30 a.m. to 4:15 p.m. When ordering bidder or non-bidder packages it is important that you include a telephone number and fax number, P.O. Box and street address so that you can receive addenda.

July 9, 2002

11-SD-5-R32.5/R38.7
11-075804
ACIMG-005-1(586)20E

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for construction on State highway in SAN DIEGO COUNTY IN SAN DIEGO FROM 0.2 KM NORTH OF THE SAN DIEGO RIVER BRIDGE TO 0.2 KM NORTH OF THE MISSION BAY DRIVE OVERCROSSING .

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on July 25, 2002, instead of the original date of July 11, 2002.

This addendum is being issued to set a new bid opening date as shown herein and revise the Project Plans, the Notice to Contractors and Special Provisions, the Proposal and Contract, and the Federal Minimum Wages with Modification Number 7 dated 7-5-02. A copy of the modified wage rates are available for the contractor's use on the Internet Site:

http://www.dot.ca.gov/hq/esc/oe/weekly_ads/addendum_page.html

Project Plan Sheet 54 is revised. A half-sized copy of the revised sheet is attached for substitution for the like-numbered sheet.

In the Special Provisions, Section 10-1.01, "ORDER OF WORK," the following paragraph is added after the fifth paragraph:

"The Contractor shall complete work on the southbound side prior to commencing work on the northbound side of Route 5."

In the Special Provisions, Section 10-1.23, "TEMPORARY CRASH CUSHION (ADIEM)," the fifth and sixth paragraph is revised as follows:

"The price quoted by the manufacturer for ADIEM-350, FOB Centerville, Utah is \$12,000.00, not including sales tax.

The above price will be firm for orders placed on or before July 31, 2003, provided delivery is accepted within 90 days after the order is placed."

Addendum No. 1
Page 2
July 9, 2002

11-SD-5-R32.5/R38.7
11-075804
ACIMG-005-1(586)20E

In the Special Provisions, Section 10-1.26, "EXISTING HIGHWAY FACILITIES," subsection "REMOVE TRAFFIC STRIPE," Temporary Crash Cushion (ADIEM)," the fourth paragraph is revised as follows:

"Waste from removal of existing yellow painted traffic stripe contains lead chromate in average concentrations greater than or equal to 5 mg/L Soluble Lead or 1000 mg/kg Total Lead. Yellow painted traffic stripe exists from Station 394+72.90 to Station 396+45.90. Residue produced from when yellow paint is removed may contain heavy metals in concentrations that exceed thresholds established by the California Health and Safety Code and may produce toxic fumes when heated."

In the Special Provisions, Section 10-1.42, "CONCRETE BARRIER," the third and ninth paragraphs are deleted.

In the Special Provisions, Section 10-2.03, "EXISTING HIGHWAY IRRIGATION FACILITIES," subsection "LOCATE EXISTING CROSSOVERS AND CONDUITS," the following paragraphs are added after the last paragraph:

"Existing irrigation crossovers may be asbestos coated pipe.

Full compensation for removal of asbestos coated pipe as directed by the Engineer will be paid for as extra work as provided in Section 4-1.03D, "Extra Work," of the Standard Specifications."

In the Proposal and Contract, the Engineer's Estimate Items 16 and 17 are revised, Items 54 and 55 are added and Item 53 is deleted as attached.

To Proposal and Contract book holders:

Replace pages 3 and 5 of the Engineer's Estimate in the Proposal with the attached revised pages 3 and 5 of the Engineer's Estimate. The revised Engineer's Estimate is to be used in the bid.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the proposal.

Submit bids in the Proposal and Contract book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This office is sending this addendum by UPS overnight mail to Proposal and Contract book holders to ensure that each receives it.

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

REBECCA D. HARNAGEL, Chief
Office of Plans, Specifications & Estimates
Office Engineer

Attachments

ENGINEER'S ESTIMATE**11-075804**

Item	Item Code	Item	Unit of Measure	Estimated Quantity	Unit Price	Item Total
1	070012	PROGRESS SCHEDULE (CRITICAL PATH METHOD)	LS	LUMP SUM	LUMP SUM	
2	070018	TIME-RELATED OVERHEAD	DAY	220		
3	074023	TEMPORARY EROSION CONTROL	M2	2000		
4	024046	TEMPORARY CONCRETE WASHOUT (PORTABLE)	LS	LUMP SUM	LUMP SUM	
5	024047	TEMPORARY CONSTRUCTION ENTRANCE (PLATES)	EA	2		
6 (S)	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM	LUMP SUM	
7 (S)	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM	LUMP SUM	
8 (S)	024048	TRAFFIC PLASTIC DRUMS	EA	14		
9 (S)	128650	PORTABLE CHANGEABLE MESSAGE SIGN	EA	2		
10 (S)	129000	TEMPORARY RAILING (TYPE K)	M	11 900		
11 (S)	024049	TEMPORARY CRASH CUSHION (TYPE ADIEM)	EA	2		
12	150656	REMOVE CABLE BARRIER	M	80		
13	150662	REMOVE METAL BEAM GUARD RAILING	M	660		
14	150666	REMOVE METAL BEAM BARRIER	M	2300		
15	150667	REMOVE DOUBLE METAL BEAM BARRIER	M	1100		
16	150710	REMOVE TRAFFIC STRIPE	M	24 500		
17	024050	REMOVE TRAFFIC STRIPE (YELLOW)	M	180		
18	153214	REMOVE CONCRETE CURB	M	280		
19	160101	CLEARING AND GRUBBING	HA	3		
20	170101	DEVELOP WATER SUPPLY	LS	LUMP SUM	LUMP SUM	

ENGINEER'S ESTIMATE**11-075804**

Item	Item Code	Item	Unit of Measure	Estimated Quantity	Unit Price	Item Total
41 (F)	024054	CONCRETE BARRIER (TYPE 60SA MODIFIED 2)	M	280		
42	024055	CONCRETE BARRIER (TYPE 60SE MODIFIED)	M	110		
43	024056	CONCRETE BARRIER (TYPE 60S MODIFIED 2)	M	930		
44 (S)	840656	PAINT TRAFFIC STRIPE (2-COAT)	M	36 800		
45 (S)	850101	PAVEMENT MARKER (NON-REFLECTIVE)	EA	13 500		
46 (S)	850111	PAVEMENT MARKER (RETROREFLECTIVE)	EA	5100		
47 (S)	024057	MODIFY RAMP METERING SYSTEM (LOCATION 1)	LS	LUMP SUM	LUMP SUM	
48 (S)	024058	MODIFY RAMP METERING SYSTEM (LOCATION 2)	LS	LUMP SUM	LUMP SUM	
49 (S)	024059	MODIFY RAMP METERING SYSTEM (LOCATION 3)	LS	LUMP SUM	LUMP SUM	
50 (S)	024060	MODIFY RAMP METERING SYSTEM (LOCATION 4)	LS	LUMP SUM	LUMP SUM	
51 (S)	024061	MODIFY RAMP METERING SYSTEM (LOCATION 5)	LS	LUMP SUM	LUMP SUM	
52 (S)	024062	MODIFY RAMP METERING SYSTEM (LOCATION 6)	LS	LUMP SUM	LUMP SUM	
53	BLANK					
54	024452	PAINT TRAFFIC STRIPE (BLACK) (1-COAT)	M	12 100		
55	999990	MOBILIZATION	LS	LUMP SUM	LUMP SUM	

TOTAL BID: _____